# BRUHATH BENGALURU MAHANAGARA PALIKE

**Yelahanka Division, Yelahanka Zone**

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/21/2017-18 Dated: 06-03-2018

## APPROVED TENDER SCHEDULE –'B'

Item No: 04

Name of Work:-Construction of RCC drain at Sanjeevappa road in ward no 04

| Sl | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved Rates Sri KISHORE KUMAR M | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 1 | KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no142, PWD SR 2016-17) | Cum | 288.00 | 90.83 | Rupees Ninety and Paise Eighty Three Only |
| 2 | KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 134 (SR 2016-17) | Cum | 288.00 | 103.67 | Rupees One Hundred Three and Paise Sixty Seven Only |
| 3 | KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3)/ PWD SR 2016-17 | Cum | 36.00 | 5391.18 | Rupees Five Thousand Three Hundred Ninety One and Paise Eighteen Only |
| 4 | KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, N | Cum | 86.40 | 6658.38 | Rupees Six Thousand Six Hundred Fifty Eight and Paise Thirty Eight Only |

| | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved Rates Sri KISHORE KUMAR M | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| | SI 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46/ PWD SR 2016-17 | Qntl. | 77.76 | 6735.59 | Rupees Six Thousand Seven Hundred Thirty Five and Paise Fifty Nine Only |
| 6 | KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters, bittresses,buttresses plinth and string course including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 15/ Item No. 4.31/ PWD SR 2016-17 | Sqm | 768.00 | 324.56 | Rupees Three Hundred Twenty Four and Paise Fifty Six Only |
| 7 | RCC Precast covering slab for drain (10cm thick ) | Sqm | 143.10 | 2194.50 | Rupees Two Thousand One Hundred Ninety Four and Paise Fifty Only |

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.